



# The Performing Arts Center


New Jersey, U.S.A.

**Turner**

## Technical Assignment 1: Construction Project Management

Eric Luttmann | Construction Management | <http://ewl5165.weebly.com>

Advisor: Dr. Somayeh Asadi



# Table of Contents

Executive Summary	1
Client Information	1
Project Delivery System	2
Staffing Plan	2
Local Conditions	3
Site Logistics Planning	3
Building Systems Summary	3
Project Schedule Summary	6
Project Cost Evaluation	6
Bibliography	8
Appendix A – Organization Structure	9
Appendix B – Staffing Plan	10
Appendix C – Site Logistics Plan	11
Appendix D - Cost & Square Foot Data	12
Appendix E – Summary Schedule	15

## Executive Summary

The Performing Arts Center will be the premier space for music and performing arts in higher education. It has been chosen to be analyzed for the Penn State Architectural Engineering Senior Thesis in addition to being the focal point of the Schreyer Honors Thesis. The AE Senior Thesis will investigate the construction of this structure in depth from preconstruction, to completion and turnover.

Technical Report One will provide overview of the project scope and reveal the conditions of how the building is constructed. Furthermore, it will reveal design purposes, owner needs and delivery method information. This report will also include project schedule summary, a technical systems summary, local site conditions, cost evaluation, site logistics and staffing.

As a space for the music department, theatre, dance, creative and performing arts, the program includes separate buildings uniquely designed around each discipline. To function as a gateway from town to campus, students can walk through the system's courtyard, while most of the building lies in the underground forum. The owner's desire to set a high precedent on this project can be characterized by the goal not to pursue LEED certification, but to exceed energy codes by 50% and "focus on maximum carbon reduction throughout the design, construction and operation of the facility" (BNIM).

The building encompasses 139,000 square feet through 9 total levels with one of the two underground levels as a massive forum. Due to exquisite material selection, complex systems, and unique construction of the building, the center totals \$140 Million. It is part of a larger enabling project which includes a Wawa market, major utility and road relocation, and transportation center development. The project is being constructed using a construction management at risk delivery method, leveraging a guaranteed maximum price (GMP) contract between Turner Construction Company and the owner. Construction began in January 2014 and will be completed by May 2017. This is critical so that the university can begin using the facility during fall semester, 2017. Since the project lies on the edge of a historical university, logistics and planning is necessary not to disrupt student and faculty life. The following report will explain the design, construction and scope of work in further detail.

## Client Information

**\* Note: The Owner has requested for undisclosed identity and location**

Due to the owner's desire to set a high precedent on this project, performance and design are paramount. The precedent set in design using geothermal heating and cooling, green roofs and envelope performance is matched with the construction goals and planning between the University and Turner Construction.

The owner needs the Performing Arts Center so that the music, theatre, dance, creative and performing arts departments can be consolidated at a central location. This building will serve as a space for rehearsal and performance from individual to group settings. It will also function as a portal from town to campus with the goal of being a transparent source of learning and experience between the artists and students passing.

For the University, schedule is the main focus of priority so that the campus runs smoothly and effectively around current construction and completion dates. Completion by May 2017 is imperative so that turnover is smooth and final punch list items are eradicated by the time students come back to campus in Fall 2017. Intertwined with the priority of schedule is logistics. To be successful, this project has been planned out to meet the restrictions of both the University and local town ordinances. As seen in Appendix 1 and discussed in the Site Logistics Section, the entire site is setup to enable safe and uninterrupted student and faculty pedestrian movement. This becomes especially important because the site is located on the threshold of campus and town. Although logistics and schedule are high priority, this project is extremely quality driven. The University will base initial pricing decisions off relationships with contractors and subcontractors that can provide the highest quality work.

## [Project Delivery System](#)

### *\*Reference Appendix A*

Turner Construction has a history of collaborating with The University to meet schedule, quality and budget needs. As familiar project partners, this allows both parties to be confident in their delivery method approach and contractual arrangements. To best complete the project, the delivery system of a CM-At Risk with GMP contract was chosen. Turner holds the risk of performance and must complete the work within the price of \$140 Million. Turner obtained the job from an RFP, was chosen for preconstruction services including schedule, budget and constructability advice and then transitioned into general contractor due its competitive bidding, expertise on the job, and quality client driven relationships. This is the traditional system utilized by the University in large projects, especially when working with Turner Construction. A benefit is that the Turner Somerset staff was involved throughout the entire process with early input from design to construction. The difficulties associated with this delivery method is that the relationship between Steven Holl, Turner and the University can become tense and strained once the price is fixed. This system means that the design by Steven Holl and consultant engineers must have been finished with little to no errors in order to maintain The University's rapid schedule goals.

Both parties excel with this delivery method due to its top-down communication stream from The University to Turner to the subcontractors. The overall contractual arrangement, seen in Appendix A, is setup so the main contract is between Turner Construction and The University. There are then individual contracts between the general contractor and subcontractors with no unique forms of collaboration or joint ventures.

## [Staffing Plan](#)

### *\*Reference Appendix B*

The staffing plan illustrates the Turner team members from the Somerset, NJ office that work onsite at the Performing Arts Center. Please reference Appendix B to see a graphical representation of the staffing. It follows a fairly traditional staff plan for large complicated projects. The engineering team is responsible for ensuring that

everything is procured and constructed according to the project specifications and architect's design. A notable feature is that a superintendent is hired entirely for quality assurance – quality control. This illustrates the importance of quality and attention to detail for finishes and material on this project. The other two superintendents are hired to lead field operations for the structural system and the MEP system. Please note that as the project progresses through construction, staffing may change to address system focus.

### Local Conditions

The existing conditions include many existing buildings, paved parking lots and existing NJ Transit lines. Beneath the man-made fill lies residual soil which overlies weathered but intact shale and sandstone bedrock. The Stockton Formation bedrock lies at a shallow depth of 9 to 25 feet. The first stratum soil conditions are described as brown, gray or reddish brown silt with clay. Water conditions indicated by boring logs illustrated dry conditions for the range of 14.1 to 25.1 feet below grade. The highest known water level was at 16.7 feet below grade. For the University parking is a major concern because the majority of the enabling site was parking space at one time. At the time of construction of the Performing Arts Center, other adjacent facilities such as the train station and Wawa will have limited parking due to the construction site takeover. Local bylaws are strict and allow for significant restrictions to construction. Difficulties include restricted deliveries during University move-in weeks, noise elimination during study periods and final exams, and a no work ordinance after 5 PM and before 7 AM. Based on schedule line items, fire protection, smoke evacuation and elevator permits are most concerning to the project.

### Site Logistics Planning

*\*Reference Appendix C*

The Performing Arts Center is tightly surrounded by two main roads and local University facilities. The highest priority of logistics is to maintain safe and effective pedestrian flow around the project site from town to campus. The green strip on the site logistics plan illustrates the temporary pedestrian sidewalk. (See Appendix C). Due to constricting area, site laydown area is limited. To enable smooth logistical practice means the team implements Lean practices including using all piping being pre-fabricated to minimize clutter onsite.

### Building Systems Summary

#### Demolition:

The owner's goal is to salvage and recycle 95% of all nonhazardous demolition materials including but not limited to mechanical equipment, concrete, insulation, roofing, plumbing fixtures and structural steel. Demolition on this job includes clearing the initial site by removing all existing structures and utilities around a 10 foot perimeter space for new building construction. Any asbestos or lead-based paint encountered will require the contractor to stop work immediately and cooperate with the owner and appropriate consultants for removal.

### Structural Steel Frame:

The structural steel frame system includes 996 tons of structural steel 100% fabricated from the BIM. A horizontal bracing system is utilized for many of the floors, especially the large courtyard area over the underground forum (See Figure 1). During main superstructure construction, three cranes were on site including the west, east and north. Two cranes are crawler cranes whereas one is Rough Terrain (RT) truck crane. When the large box girders above the forum were installed, a specialty 600 ton capable crane came to site. The flooring slabs will be composed of composite steel floor deck that ranges from 2" to 5" thick slab with 18-22 corrugated steel.




Figure 1: Structural Steel Frame model provided by Turner

### Cast In Place Concrete System:

The walls, foundation walls, columns and footings of the building are all cast in place concrete. Many beams and structural slabs are post-tensioned, cast-in-place concrete as well. The formwork for most structural elements is traditional timber formwork. For the architectural concrete finish on many interior walls, pre-fabricated board forms are delivered from Massachusetts. This means that the walls have a concrete, ripple finish along the interior which will be the final finish product. All formwork is pre-fabricated. On average, 13 trucks of concrete arrive 3-4 times a week in order to pour 100 yards of concrete a day.

### Pre-Cast Concrete System:

All pre-cast concrete is cast within 500 miles of the project site. The concrete specification is to utilize Portland Cement ASTM C 150. Anchorage and connection will be through bolting, welding or grouting. The 2 crawler cranes that are located in the east and north are utilized to install pre-cast elements including beams and slabs.

### Mechanical System:

The mechanical system is enabled through the use of the geothermal heating and cooling wells. A ground-coupled heat pump system consisting of heat pumps, circulating pumps and a ground coupled heat exchanger enables the closed loop system. In the majority of the rooms are overhead VAV boxes except for the use of floor supply in select areas. Radiant heat is leveraged in music offices, practice rooms, the forum and the CoLab. Most of the

corridors include both overhead VAV boxes and radiant heat to enable the feasibility for completely geothermal dependency or traditional means.

### Electrical System:

The power distribution system is delivered from the campus by 4.16kV feeders. These feeder services go directly to the north face of the subbasement level where they meet the main switchgear room at two service tap boxes. Emergency power is supplied to areas that need egress lighting and fire alarm system equipment. Standard dry-type transformers serves all theatrical lighting dimmer racks and LED theatrical lighting. Another major electrical concern is power to the acoustical equipment which will be served from 480-208/120V transformers.

### Masonry & Curtain Wall System:

The façade system is composed of Lecce Limestone cladding and glazed curtain wall system. The masonry façade features 2' high by 3' wide limestone panels that are supported by or non-corrosive, stainless steel anchors so the loading is transferred to the cast-in-place concrete wall system. (See figure 2 for connection detail of wall system). The curtain wall system varies between vision glass curtain wall system and translucent curtain wall glazing. Both are low-iron insulating glass units. These are built to custom profile steel mullions and glazing frames of built-up steel bar stock construction. The design for the vision glass is to allow for students to visualize the rehearsal and practice of students and learn from their exposure.

Concrete masonry unit (CMU) walls utilized as load bearing walls for floor decking. CMU is fully grouted and connected to steel decking through steel angles. Standard board scaffolding with steel tubing is used on this project.




Figure 2: 100% Contract Documents – Volume 6 – Turner Construction – Exterior Wall Sections – A300

## Project Schedule Summary

*\*Reference Appendix E*

Planning and design for the Performing Arts Center began in early 2008. The construction duration began in January 2014 and is projected to be completed earlier than anticipated, by May 2017. The phase of shop Drawings, submittals packages and approvals runs from January 2014 until October 2016. Visual mockups are constructed from July 2015 until October 2015. Materials are fabricated from June 18<sup>th</sup> 2015 until January 2016. Physical construction did not begin onsite until May 2015. The University would like the facility to be open by September 2017, therefore temporary certificate of occupancy should be finalized by July 24, 2017 at the latest. The summary schedule (Appendix D) is broken down by the major milestones throughout the entire lifecycle of The Performing Arts Center. The construction sequencing is based around each individual building, the DRUM, the Dance Theatre, the Forum, The Arts Tower, and the Music building.

The overall superstructure is to be complete on December 3<sup>rd</sup>, 2015 with the superstructure completion of the Lewis Arts Tower. Major milestones for the separate buildings include permanent power being energized on December 7<sup>th</sup>, 2015, the superstructure of the Theater/Dance building to be completed Oct 28<sup>th</sup>, 2015, the superstructure of the music building to be completed Oct 20<sup>th</sup>, 2015 and enclosure of the Forum space on May 24<sup>th</sup>, 2016. Please reference the summary schedule in Appendix D for more information.

## Project Cost Evaluation

*\*Reference Appendix D*

While the Performing Arts Center only totals 139,000 square feet, the total construction cost rises to \$140 million. This is the equivalent of \$1007/SF. When counting the enabling project, the entire project reaches \$300 million and an equivalent to \$2,158 per square foot. For the Performing Arts Center itself, 60% of the project is material cost which is vastly larger than most jobs because of specialized materials and construction seen in the job. Examples include exterior Lecce Limestone cladding, 100% roof garden and architectural concrete walls seen throughout the building. In addition, a 110 well geothermal ground-coupled heat pump system is installed underneath part of the enabling project. These systems entail large up-front costs, but allow for return on investment over the long term. Another unique feature of the project is that acoustical provisions made up for 10% of the entire project cost.

The cost breakdown by system can be seen in Table 1. Appendix B illustrates the square foot estimate of this project based on an auditorium model. This model can be assumed because of the zoning designation as theatre/performance space and the focus on acoustical performance throughout the project. Furthermore, the majority of space is utilized for performance or rehearsal space. However, the R.S. Means estimate proves to be extremely low compared to the high actual cost / SF for this project. R.S. Means cost data only reaches 16% of the true cost of this project, a strikingly low estimate because of the usage of basic materials. The complex system choice and high quality material, design and construction enabled by the owner explains the difference in cost compared to the R.S. Means estimate. Furthermore,



R.S. Means did not offer a model that resembled the diverse usage or occupancy type of the building that included specialized construction such as acoustical isolation of rooms and structural components that hang individual rehearsal rooms.


Table 1: Major system breakdown costs including material and labor cost

The Performing Arts Center System Breakdown Costs	
Architectural (Carpentry, flooring, paint, etc.)	\$70 Million
Structural System	\$30 Million
Mechanical (plumbing included)	\$25 Million
Electrical System	\$15 Million


## Bibliography

"Lewis Center for the Arts | BNIM." Lewis Center for the Arts | BNIM. N.p., n.d. Web. 16 Sept. 2015.

## Appendix A | The Performing Arts Center Organization Structure



Appendix B | Staffing Plan | Turner Construction Co. (Somerset, NJ)




## Appendix C | Site Logistics Plan

Campus



Town

- Key:**
- 1: Masonry Lay Down Area
  - 2: Concrete Staging Area
  - 3: Paved road with faculty/public access
  - 4: Temp. Pedestrian Sidewalk
  - 5: Construction Temp. Road
  - 6: Trailers
  - 7: Lecce Stone Staging area
  - 8: Temporary Power
  - 9: Geothermal wells
  - 10: Restaurant/Cafe Renovation (Enabling)
  - 11: Construction Gate & Exit(s)
  - 12: Curtain wall Staging Area



## Appendix D | Square Foot Estimation Data

### The Performing Arts Center – Square Foot Schematic Estimate

Cost Data based off of:

Phelan, Marilyn, AIA. R.S. Means Square Foot Costs 2015. N.d. Construction Cost Data. Norwell, Massachusetts.

The Performing Arts Center - Square Ft. Schematic Estimate						
RS Means Source		R.S. Means Square Foot Costs 2015		Model #		M.040 Auditorim
Page(s)		86-87		Ext Wall Type		Face Brick with Concrete
Area		125,900		Frame		Steel Frame
Area Falls Between		125,900		and		+
				Base cost per SF		\$137.40
Cost Adj Type:		Perimeter		Per SF Adj		\$45.35
Cost Adj Type:		Story Height		Per SF Adj		-\$10.00
				Adj Base cost per SF		\$172.75
Base Bldg Cost		172.75	x	125,900	=	\$21,749,225.00
Basement Cost		30.15	x	30,023	=	\$905,193.45
		Basement Cost / SF		Basement Area		
				Total Base Bldg Cost		\$22,654,418.45
Additive Source	Type	Quantity	Price/Unit			Total
RS Means Additions	Closed Circuit Sur	3	1975	Amount		\$5,925.00
RS Means Additions	Seating	200	320	Amount		\$64,000.00
RS Means Additions	Emergency Lighting	100	\$780	Amount		\$78,000.00
RS Means Additions	Sound System	2700	\$130	Amount		\$351,000.00
				New Subtotal Cost		\$23,153,343.45
Multiplier Type	Time			Value		1.05
Multiplier Type	Location			Value		0.94
				New Subtotal Cost		\$22,852,349.99
				Total Cost	\$	\$22,852,349.99

				The Performing Arts Center   12	
	Assembly	% of Total		Cost per SF	Total Cost
A	Substructure	7.50%		\$13.61	\$1,713,926.25
B	Shell			\$45.71	\$0.00
B10	Superstructure	8.80%		\$19.41	\$2,011,006.80
B20	Exterior Enclosure	21.70%		\$20.46	\$4,958,959.95
B30	Roofing	4.60%		\$5.84	\$1,051,208.10
C	Interiors	18.80%		\$26.19	\$4,296,241.80
D	Services			\$0.64	\$0.00
D10	Conveying	2.70%		\$6.90	\$617,013.45
D20	Plumbing	9.50%		\$23.33	\$2,170,973.25
D30	HVAC	9.60%		\$2.91	\$2,193,825.60
D40	Fire Protection	2.90%		\$15.69	\$662,718.15
D50	Electrical	13.90%		\$2.93	\$3,176,476.65
E	Equipment & Furnishings	0.00%		\$0.00	\$0.00
F	Special Construction	0.00%		\$0.00	\$0.00
G	Building Sitework	N/A		N/A	N/A
	Additions	N/A		N/A	N/A
				<b>Subtotal</b>	<b>\$22,852,349.99</b>
	<b>Jobsite OH &amp; GC's</b>	20.00%			\$4,570,470.00
	<b>Contractors Fee</b>	5.00%			\$1,142,617.50
	<b>Designer's Fee</b>	5.00%			\$1,142,617.50
				<b>Total</b>	<b>\$29,708,054.98</b>

### Assumptions and Clarifications:

Assume building type is M.040 Auditorium

Assume Face Brick Concrete Block Back Up based on the given parameters and actual Lecce Limestone façade.

Assume steel frame structural system

Assume maximum ceiling height of 16'

**Square Foot Takeoff and Calculations:**

	Perimeter	Area	
Forum Level	996.75'	49,860	SF Takeoffs
Mezzanine Level	(All from above)	16,705	3,751
			891
			630
			11,433
Plaza Level		16,262	4,711
			2,345
			4,369
			3,065
Level 2 Plan		24,715	1,772
			532
			4,447
			15,522
Level 3 Plan		18,357	4,214
			13,565
			1,532
			3,260
	<b>Total Area:</b>	<b>125,899</b>	
	<b>Perimeter:</b>	<b>996.75'</b>	



# Appendix E | The Performing Arts Summary Schedule

